



Issue date: October 4, 2019

ADDENDUM #4


JURUPA VALLEY BOXING CLUB
PARKING LOT IMPROVEMENTS
5646 Mission Boulevard, Jurupa Valley Ca 92509

Project # FM08190008454

Item 1: The following change is made to the existing Bid Documents page BD25:

BD-25 Bid Schedule Form - changed to include Item No: 1 through 31. Please include the TOTAL SUM BID, ITEMS 1 THROUGH 31.

BD-4 – Bid closing deadline to remain unchanged. All bids due on or before 10a.m. on 10/07/19. Bid location also remains unchanged and Bidder assumes sole responsibility for timely receipt of its Bid. Refer to Notice Inviting Bids.


Issued By: Blanca Limon
Project Manager III
951-955-9138

**BID SCHEDULE
FOR
JURUPA VALLEY BOXING CLUB PARKING LOT IMPROVEMENTS**

The undersigned hereby proposes to furnish all labor, materials, equipment and methods necessary for constructing all Work specified, all in strict accordance with these Contract Documents, at the bid prices and the Completion Date set forth hereafter. Quantities are estimates and must be verified by the contractor. If there is a discrepancy between the plans and the bid schedule, the plans prevail. Estimates are plus or minus 10% and adjustments to the contract for amounts over or under the estimate will only be made when the quantity adjustments exceed the 10% threshold. The undersigned also acknowledges that all bid prices include sales tax and all other applicable taxes and fees.

Item No.	Description	Unit	Estimated Quantity	Unit Prices (in figures) Dollars/Cents	Item Total (in Figures) Dollars/Cents
1	Mobilization, Permits	LS	1		
2	Traffic Control	LS	1		
3	Dust Abatement	LS	1		
4	Encroachment Permit/Drain	LS	1		
5	Water Pollution Control	LS	1		
6	Soils & Material Testing	LS	1		
7	Clearing and Grubbing	LS	1		
8	Excavation	CY	1380		
9	Remove Existing Asphalt Concrete Pavement	SY	97		
10	Remove Existing Chain-link Fence	LF	315		
11	Place A.C. Pavement (8835 sf x 0.35' Thk)	TON	232		
12	Place Aggregate Base	CY	164		
13	Fog Seal	GAL	50		
14	Construct 6" Type A-6 Curb and Gutter	LF	20		
15	Construct 6" Type D Curb	LF	52		
16	Construct 6" Type D Curb, Modified w/2' openings	LF	93		
17	Construct Flush Curb	LF	17		
18	Construct 8"x12" Concrete Mow Strip	LF	200		
19	Construct Concrete Ribbon Gutter	LF	57		

Item No.	Description	Unit	Estimated Quantity	Unit Prices (in figures) Dollars/Cents	Item Total (in Figures) Dollars/Cents
20	Install 2"X 4" Redwood Header	LF	24		
21	Construct Private Through Curb Drain – 3-1/2"x12" CIP	EA	1		
22	Construct 4" Concrete Pad w/4"-6" River Cobbles Embedded as Shown on Detail	SF	160		
23	Construct 6' high Wrought Iron Fence	LF	230		
24	Paint Parking Spaces, Handicap & No Parking Area Striping	LS	1		
25	Install Handicap Signage at Parking Lot Entrance and Handicap Parking Space	EA	2		
26	Install 18"X18" Brooks Catch Basin w/ Steel Grate or Approved Equal	EA	1		
27	Install Myers SRM4PC-2 0.4 HP Sump Pump (80 GPM @ 5' Head, or Approved Equal	EA	1		
28	Install Solar Powered Parking Lot Lights	EA	4		
29	Bioretention Basin Bio-material, gravel and underdrain	LS	1		
30	Landscape & Irrigation Plan implementation	LS	1		
31	Install Control Panel, Controller, Conduit & Wire as shown on Electrical Plan				

**Item Total (in Figures)
Dollars/Cents**

TOTAL SUM BID, ITEMS 1 THROUGH 31: _____
Words
 _____ (\$ _____)
Figures